

NOTES:

- 1. CEMENT CONCRETE SHALL BE CL 4000, 3-DAY PAVEMENT MIX.
- 2. NEW MANHOLES SHALL RECEIVE THE SAME CONCRETE & REINFORCING STEEL SURROUND AS SHOWN ABOVE FOR ADJUSTED MANHOLES.
- 3. CONCRETE COLLAR SHALL BE CONSTRUCTED WITH POINTS PARALLEL AND PERPENDICULAR TO TRAFFIC FLOW.
- 4. SEAL BETWEEN RISERS AND CASTING TO BE MASTIC.



CEMENT COLLAR FOR MANHOLES

STANDARD PLAN: CITY ENGINEER APPROVAL: Longview: C.B.

DATE: **FEB. 2007** Kelso: **S.Z.**