



NOTES:

1. COLLAR REQUIRED EVERY 50' MAX., CITY MAY REQUIRE ADDITIONAL COLLARS.
2. ALL PIPE TO BE RESTRAINED JOINT.
3. CONTRACTOR SHALL PROVIDE MATERIAL SUBMITTALS ON PROPOSED PIPE RESTRAINT PRIOR TO CONSTRUCTION.



**SEWER PIPE ANCHOR
(SLOPES 15% OR MORE)**

STANDARD PLAN:
SS - 250

CITY ENGINEER APPROVAL:

DATE: **FEB. 2008**

Longview: **C.B.**

Kelso: **S.Z.**