

WATER NOTES ADDITIONAL

1. CONNECTION TO THE WATER SYSTEM SHALL BE INSPECTED BY PUBLIC WORKS DEPARTMENT PRIOR TO BACKFILL 48 HOURS (2 WORKING DAYS) NOTICE FOR INSPECTION.
2. ALL WATER SYSTEM FLUSHING, INCLUDING FIRE LINES, SHALL BE SCHEDULED THROUGH THE PUBLIC WORKS DEPARTMENT WHO WILL IN TURN SCHEDULE THE WATER DEPARTMENT TO BE PRESENT TO RECORD WATER USED AND TO OPERATE VALVES.
3. UTILITY PERMITS MUST BE APPLIED AND PAID FOR PRIOR TO ANY CONNECTIONS BEING MADE TO EITHER THE WATER OR SEWER SYSTEM.
4. BACKFLOW DEVICES REQUIRED ON ALL COMMERCIAL, IRRIGATION AND FIRE SERVICE CONNECTIONS TO THE CITY SYSTEM. CITY TO DETERMINE LEVEL OF HAZARD & DEVICE REQUIRED DURING PLAN REVIEW/DESIGN.
5. ONLY CITY WATER DEPARTMENT PERSONNEL SHALL OPERATE CITY VALVES.
6. SHUT DOWNS OF THE WATER SYSTEM FOR CONNECTIONS WILL BE DONE BETWEEN TUESDAY THROUGH THURSDAY FROM 8 AM TO 4 PM. MAX TIME THE WATER MAY BE OFF IS 4 HOURS.
7. SUBMITTALS AND SHOP DRAWINGS MUST BE APPROVED BEFORE THE SHUT DOWN IS SCHEDULED. CONTRACTOR IS REQUIRED TO NOTIFY THE CUSTOMERS AFFECTED 2 WORKING DAYS IN ADVANCE IN WRITING WITH CITY APPROVED LETTER. CONTRACTOR SHALL PRE-BOLT ALL MATERIALS & HAVE THE ASSEMBLY INSPECTED PRIOR TO ANY SHUT DOWN OF THE CITY SYSTEM. ALL BOLTS THAT WILL NOT UNDERGO PRESSURE TESTING SHALL BE TORQUE TIGHTENED TO MANUFACTURERES RECOMMENDATIONS IN THE PRESENCE OF THE INSPECTOR.
8. METERS LARGER THAN 1" WILL BE SUPPLIED BY THE CONTRACTOR.
 - A. MUST BE DELIVERED TO THE WATER DEPARTMENT SHOP FOR ACCURACY TESTING AT LEAST ONE WEEK PRIOR TO INSTALLATION DATE.
 - B. MUST BE INSTALLED BY THE CONTRACTOR.
9. (City of Longview Only) CONCRETE COLLARS SHALL BE STAMPED WITH PIPE SIZE & FLOW DIRECTION. (CITY SHALL SUPPLY/LOAN STAMPS)



WATER GENERAL NOTES

STANDARD PLAN: W - 001	CITY ENGINEER APPROVAL:
DATE: FEB. 2008	Longview: C.B.
	Kelso: S.Z.