



**NOTES:**

1. USE 3/4", CLEAN, SCH. 80 OR BETTER PVC MATERIAL FOR PIPE AND BENDS.
2. CONTRACTOR TO ASSEMBLE FOR SAMPLING TO OBTAIN BACTERIA TEST.
3. TEST STATION TO BE INSTALLED AFTER FLUSHING AND TESTING IS COMPLETE.
4. CONTRACTOR IS RESPONSIBLE TO SUPPLY, INSTALL AND REMOVE TEST STATION.
5. TO BE FLUSHED WITH A MINIMUM OF 50 mg/L OF CHLORINATED WATER PRIOR TO INSTALLING.



**TEST STATION DETAIL**

STANDARD PLAN:  
**W - 660**  
 DATE: **FEB. 2007**

CITY ENGINEER APPROVAL:  
 Longview: **C.B.**  
 Kelso: **S.Z.**