

7-14 HYDRANTS

Construction Requirements

Section 7-14.3(6); Hydrant Extensions

This section is supplemented with the following:

Hydrant extensions will not be allowed for newly constructed hydrants. The large port on the hydrant shall face the road.

7-15 SERVICE CONNECTIONS

Section 7-15.3; Construction Requirements

Paragraph 1 is replaced with the following:

All service connections to water mains shall be made using saddles as specified and be of the size and type suitable for use with the pipe being installed. Service pipelines shall be installed perpendicular to the main, unless otherwise shown in the plans.

Water meter service shall not conflict with electric/gas services, required 4' horizontal and 12" vertical separation from other utilities for Longview (5' horz. and 18" vert. for Kelso). (10' horizontal and 18" vertical from sanitary sewer)

PERMISSABLE HYDRANT LOCATION NOTE (construction water)

Contractor shall apply for hydrant permit thru the City Water Department if construction water is needed.

No meters installed without fee's being paid in full.

City to determine location for all hydrant meters.

WATER NOTES ADDITIONAL

1. Connection to the Water System shall be inspected by Public Works Department. 48 Hours (2 working days) notice for inspection.
2. All water system flushing, including fire lines, shall be scheduled through the Public Works Department who will in turn schedule the water department to be present to record water used and to operate city valves.
3. Utility permits must be applied and paid for prior to any connections being made to either the water or sewer system.
4. All backflow devices must be tested and certified by a stated certified tester prior to the water services being activated for use.
5. Only City Water Department personnel shall operate city valves.
6. Shut downs of the water system for connections will be done between Tuesday and Thursday from 8 AM and 4 PM. Max time the water may be off is 4 hours without prior approval.
7. Submittals and shop drawings must be approved before the shut down is scheduled. Contractor is required to notify the customers affected 2 working days in advance in writing with city approved letter.
8. Meters larger than 1" will be supplied by the contractor.
 - a. Must be delivered to the Water Department shop for accuracy testing at least one week prior to installation date.
 - b. Must be installed by the contractor.
 - c. Must have approved submittal



WATER SPECIFICATIONS (4 OF 5)	
STANDARD PLAN: W - 703	CITY ENGINEER APPROVAL:
DATE: FEB. 2008	Longview: C.B.
	Kelso: S.Z.