

The Longview Police Department, Fire Department, Com Center and Engineering Department shall be notified 24 hours in advance of closing any street or alley to traffic. A traffic control plan is required to be submitted to the Engineering Department for review and approval prior to scheduling any street or pedestrian way closure. All Traffic control shall be in accordance with the latest edition of the MUTCD Standards. All traffic control shall be properly lighted for nighttime use.

All excavations shall be backfilled at days end, temporarily patched or plated to the satisfaction of the Engineering Department unless otherwise approved by the City of Longview Engineering Department. All backfill within the City right of way, City streets, City alleys and City easements shall be crushed surfacing top course meeting the specification for CSTC in the Standard Specifications. No excavation shall be left in a hazardous condition outside of normal work hours unless properly protected to the satisfaction of the Engineering Department. This includes all work within the City of Longview Right of Way. No sidewalks shall remain closed for more than one week without written approval from the Engineering Department. Temporary sidewalk closures shall be properly marked in accordance with the required, approved closure plan.

Pavement Replacement: Cement concrete pavement and Asphalt pavement shall be replaced to a depth of two inches thicker than original pavement. Full panel replacement will be required for concrete replacement unless otherwise approved by the Engineering Department. All AC edges will be saw cut, sealed and sanded at the completion of the permanent patch. In gravel alleys, the permittee shall replace the crushed surfacing materials with ten inches of CSBC and two inches of CSTC. Twelve inches of CSTC may be used if prior approval is obtained from the Engineering Department. AC pavement shall be re-cut 1 foot either side of the disturbed trench prior to final paving. Temporary patches can remain no longer than three weeks before permanent paving is completed. Temporary patching shall be performed the same day as the excavation is performed unless otherwise approved by Engineering.

Daily clean up of the construction area shall be performed to eliminate all rock, debris, dirt, mud, sand etc. from the sidewalk, street and drainage ways. This shall be performed by sweeping or other approved methods to accomplish the clean-up to the satisfaction of the Engineering Department.

The underground utilities coordinating council (1.800.424.5555) MUST be contacted two full working days prior to proceeding with any excavation associated with this permit.

Any use of City water requires a permit. Call 360.442.5700 for details and application.

A copy of all permits and project sketches, plans and material submittals shall be available at the job site at all times.

Upon completion of the work under this permit the applicant shall submit as-built drawings (as required) within three weeks of completion per the submittal process.

Contact Longview Parks Department 360.442.5422 for any work around City trees or if any tree removal is to be performed for City requirements and approval.

Contact the City Solid Waste Coordinator 360.442.5222 for any work interfering with normal garbage service and if any alley or street is to be closed or restricted.



GENERAL PERMIT PROVISIONS (2 OF 3)

STANDARD PLAN: PN - 051-L	CITY ENGINEER APPROVAL:
DATE: FEB. 2008	Longview: C.B.
	Kelso: