

SANITARY SEWER CONSTRUCTION NOTES

TRACER WIRE SHALL BE INSTALLED ALONG THE TOP OF ALL PIPE. EXTEND THE TRACER WIRE INTO MANHOLES AND ALL OTHER STRUCTURES, THEN UP THE INSIDE WALL OF STRUCTURES AND ATTACH THE WIRE TO THE TOP INSIDE OF THE STRUCTURE. PROVIDE 3 FEET OF COILED TRACER WIRE SLACK ATTACHED TO THE TOP INSIDE OF THE STRUCTURE.

MANHOLES SHALL BE ADJUSTED TO GRADE FOLLOWING PAVING. ADJUST USING AN APPROVED FOUR-POINT ADJUSTMENT SYSTEM SUCH AS THE RIMRISER SHIMLESS ADJUSTMENT SYSTEM, OR APPROVED EQUAL.

SANITARY SEWERS AND APPURTENANCES SHALL BE CLEANED, AIR TESTED AND DEFLECTION TESTED AFTER BACKFILLING. THE LOW PRESSURE AIR TEST METHOD SHALL BE USED. TV INSPECTION SHALL BE PERFORMED AFTER CLEANING, TESTING AND CORRECTIONS ARE COMPLETE. CLEANING, AIR TESTING, INFILTRATION TESTING, DEFLECTION TESTING, AND TV INSPECTION SHALL BE COMPLETED PRIOR TO PAVEMENT RESTORATION OF THE TRENCH. AN ELECTRONIC COPY OF THE TV INSPECTION VIDEO AND THE TV INSPECTION REPORT SHALL BE PROVIDED TO THE INSPECTOR. TOP LIFT OF PAVING SHALL NOT BE PLACED UNTIL THE INSPECTOR HAS APPROVED THE TV INSPECTION.

ALL MANHOLES SHALL BE WATERTIGHT. FOLLOWING BACKFILL AND PRIOR TO FINAL PAVING, PERFORM VACUUM TESTING ON MANHOLES PER THE REQUIREMENTS OF THE SUPPLEMENT TO STANDARD PLAN B-15.20-01.

AS-BUILT DRAWINGS AND TV REPORTS SHALL BE PROVIDED PRIOR TO FINAL ACCEPTANCE.

N.T.S.



SANITARY SEWER GENERAL NOTES

CITY OF KELSO
DEPARTMENT OF
COMMUNITY DEVELOPMENT
& ENGINEERING

CITY ENGINEER APPROVAL: Michael Kardas, P.E.

x. 

STANDARD PLAN NO.

KSS-000-21

DATE:

MAY 2021