



NOTES:

1. ALL FITTINGS SHALL BE PVC.
2. USE 1-RT BOX IN NON-TRAFFIC AREAS ONLY.
3. 1-RT BOX FOR 6" LATERAL ONLY.
4. CLEANOUT COVER SHALL BE MARKED "SEWER" OR "S" OUT IS LOCATED OUTSIDE OF SIDEWALK EXTENTS.
5. A CONCRETE COLLAR SHALL BE 3,000 PSI COMMERCIAL GRADE.
6. TO CONNECT TO EXTG STUBOUTS OR NEW CUT-IN TEES USE FERNCO STRONGBACK RC 1000 REPAIR COUPLINGS OR APPROVED EQUAL.
7. TAPS ARE ONLY PERMITTED ON EXISTING .8" OR LARGER, MAINLINES. TAPS SHALL BE WITH ROMAC SADDLE OR EQUIVALENT.

N.T.S.



CITY OF KELSO
DEPARTMENT OF
COMMUNITY DEVELOPMENT
& ENGINEERING

6" SANITARY SIDE SEWER
CITY ENGINEER APPROVAL: Michael Kardas, P.E.
x *[Signature]*

STANDARD PLAN NO.
KSS-020-21
DATE:
MAY 2021